





02/03/2021





GENERAL NOTES

1) ALL BARE SOILS WITHIN THE LIMITS OF WORK THAT ARE NOT DESIGNATED AS PLANT BEDS OR PERRENIAL SEED BEDS SHALL BE SOWN WITH TURFGRASS, NEW ENGLAND WILDFLOWER MIX OR NORTHEAST CONSERVATION/WILDLIFE SEED MIX. ALL SEEDING SHALL BE IN ACCORDANCE WITH THE TECHNICAL NOTES BELOW:

TECHNICAL NOTES FOR TURFGRASS & PERENNIAL SEEDING:

- 1) SCOPE OF WORK: FOR THIS PROJECT, THE WORK SHALL INCLUDE SEEDING AREAS DENUDED BY CONSTRUCTION.
- 2) ALL AREAS SHALL BE SEEDED WITHIN 30 DAYS AFTER FINISHED GRADES ARE ESTABLISHED AND OTHER ELEMENTS INCLUDED IN THIS CONTRACT ARE CONSTRUCTED.

3) SEED SPECIFICATIONS:

- A) CERTAIN AREAS ON THE PLAN SHALL BE SEEDED WITH PERENNIAL SEED MIXES AS LABELED ON SHEET L-1. THESE SEED MIXES SHALL BE SUPPLIED BY NEW ENGLAND WETLAND PLANTS, AMHERST, MA, PHONE # 413-548-800. PREPARE SOIL AND SOW SEED IN ACCORDANCE WITH THIS COMPANY'S INSTRUCTIONS FOR EACH TYPE OF SEED MIX.
- B) TURFGRASS: AREAS RECEIVING FULL SUN OR PART SHADE

FESCUE/BLUEGRASS/PERENNIAL RYEGRASS MIXTURE: MIXTURE REQUIREMENTS ARE AS FOLLOWS (WITH APPROXIMATE PERCENTAGES):

35% FINE FESCUE (ENDOPHYTIC)
35% KENTUCKY BLUEGRASS

30% PERENNIAL RYEGRASS (ENDOPHYTIC)

C) TURFGRASS: AREAS RECEIVING MOSTLY SHADE:

FESCUE/PERENNIAL RYEGRASS MIXTURE:

MIXTURE REQUIREMENTS ARE AS FOLLOWS (WITH APPROXIMATE PERCENTAGES):

90% FINE FESCUE (ENDOPHYTIC)
10% PERENNIAL RYEGRASS (ENDOPHYTIC)

- D) ANY PROPOSED SUBSTITUTIONS SHALL BE PRESENTED TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO SEEDING.
- E) ALL TURFGRASS SEED SHALL HAVE A MINIMUM PURITY OF 98 PERCENT AND A GERMINATION RATE OF 85
- F) ALL TURFGRASS SEED SHALL BE LABELED TO SHOW THAT IT IS WITHIN THE REQUIREMENTS OF THE USDA AS TO PURITY, GERMINATION, AND PRESENCE OF RESTRICTED OR PROHIBITED WEEDS.
- 4) <u>BED PREPARATION FOR AREAS TO BE SEEDED WITH TURFGRASS:</u> A ROTOVATOR, CHISEL PLOW, OR CULTIVATOR SHALL BE USED TO WORK THE SOIL TO A DEPTH OF SIX INCHES. AFTER THIS OPERATION, REMOVE AND DISPOSE OF STICKS, STONES OVER 1 INCH DIAMETER, AND RUBBISH TO A MINIMUM DEPTH OF TWO INCHES.
- 5) <u>LIME AND NUTRIENTS FOR TURFGRASS AREAS:</u> LIME SHALL BE GROUND DOLOMITIC LIMESTONE, APPLIED AT THE RATE OF 50 POUNDS PER 1000 SQUARE FEET. LIME SHALL BE WELL-MIXED INTO THE TOP THREE INCHES OF LOAM.
- 6) <u>FERTILIZER FOR TURFGRASS AREAS:</u> FERTILIZER SHALL BE A COMMERCIAL GRADE WITH A MINIMUM OF 50 PERCENT OF THE NITROGEN COMPONENT IN A CONTROLLED RELEASE FORM LABELED TO RELEASE NITROGEN FOR A MINIMUM OF SIX WEEKS. FERTILIZER SHALL HAVE AN N/P/K RATIO IN THE RANGE OF 1:1:1 TO 1:2:2. IT SHALL BE APPLIED AT A RATE WHICH ACHIEVES ONE POUND OF NITROGEN PER 1000 SQUARE FEET.
- 7) <u>SEEDING PROCEDURE FOR TURFGRASS:</u> SOWING OF SEED SHALL BE DONE ONLY AFTER THE PREPARED SOIL, TO WHICH LIME AND FERTILIZER HAVE BEEN ADDED AS SPECIFIED, HAS BEEN THOROUGHLY SETTLED BY RAINFALL OR ARTIFICIAL WATERING, IMMEDIATELY BEFORE ANY SEED IS SOWN, THE GROUND SHALL BE SCARIFIED AS SPECIFIED. LAWN AREAS SHALL BE SEEDED EVENLY WITH A MECHANICAL SPREADER. SEED MIXTURES SHALL BE SOWN AT A RATE OF 5 POUNDS PER 1000 SQUARE FEET. AFTER SEEDING, THE LAWN SHALL BE LIGHTLY RAKED, ROLLED WITH A 200-POUND ROLLER, AND WATERED WITH A FINE SPRAY. THIS METHOD OF SEEDING MAY BE VARIED AT THE DISCRETION OF THE CONTRACTOR ON HIS OWN RESPONSIBILITY TO ESTABLISH A SMOOTH, UNIFORMLY GRASSED LAWN.
- 8) SEED FOR PERMANENT TURFGRASS SHALL ONLY BE SOWN FROM THE THIRD WEEK IN APRIL THROUGH JUNE AND DURING THE MONTH OF SEPTEMBER.
- 9) TEMPORARY SEEDING FOR EROSION CONTROL: IN THE EVENT THAT THE CONTRACT IS SUSPENDED, TEMPORARY SEEDING SHALL BE USED ON ANY BARE AREAS THAT MAY BE SUBJECT TO EROSION AND WHERE TEMPORARY VEGETATION CAN BE USED TO RETARD EROSION FROM 2 TO 12 MONTHS. THE SEED TYPE USED FOR TEMPORARY COVER SHALL BE 100 PERCENT TALL FESCUE APPLIED AT A RATE OF 300 POUNDS PER ACRE.
- 10) MAINTENANCE: MAINTAIN THE TURFGRASS FROM TIME OF INSTALLATION UNTIL THE FINAL INSPECTION IMMEDIATELY PRIOR TO THE BEGINNING OF THE GUARANTEE PERIOD. MAINTENANCE SHALL INCLUDE WATERING OF TURF AREAS, REPAIRS TO TURF AREAS, AND OTHER NECESSARY OPERATIONS. THE MAINTAINED TURF AREAS SHALL BE MOWED TO A UNIFORM HEIGHT OF APPROXIMATELY TWO AND ONE—HALF INCHES. MOWING SHALL BE PROVIDED AS REQUIRED SO THAT THE TURF NEVER EXCEEDS FOUR INCHES IN HEIGHT. TURF SHALL BE PROTECTED AND REPLANTED AS NECESSARY TO ESTABLISH A UNIFORM STAND OF THE SPECIFIED TURF AND UNTIL ACCEPTANCE. SCATTERED BARE SPOTS,NONE OF WHICH IS LARGER THAN ONE SQUARE FOOT, WILL BE ALLOWED UP TO A MAXIMUM OF THREE PERCENT OF ANY TURF AREA. WHEN TURF AREAS ARE READY FOR FINAL INSPECTION, THE MAINTAINED TURF AREAS SHALL BE NEATLY MOWED TO THE UNIFORM HEIGHTS AS NOTED ABOVE. THE LAWNS SHALL BE CONSIDERED ESTABLISHED ONLY WHEN THE SPECIFIED GRASS IS VIGOROUS AND GROWING WELL IN ADDITION TO MEETING THE OTHER REQUIREMENTS SPECIFIED. AT THE TIME OF ACCEPTANCE FOLLOWING FINAL INSPECTION, THE CONTRACTOR IS RELIEVED OF ROUTINE MAINTENANCE RESPONSIBILITIES FOR THE TURF UNDER THIS CONTRACT.
- 11) <u>FINAL INSPECTION, CLEANUP AND COMPLETION:</u> FINAL INSPECTION SHALL BE FOR THE COMPLETED LANDSCAPE AND SHALL BE MADE AT THE CONCLUSION OF THE LANDSCAPE WORK. UPON COMPLETION OF THE WORK, THE CONTRACTOR SHALL REMOVE FROM THE SITE ALL EQUIPMENT AND OTHER ARTICLES USED. ALL EXCESS SOIL, STONES, AND DEBRIS SHALL BE REMOVED FROM THE SITE. ALL WORK AREAS SHALL BE LEFT IN A CLEAN AND NEAT CONDITION. ALL DAMAGE TO EXISTING CONSTRUCTION CAUSED BY THE LANDSCAPING OPERATIONS SHALL BE REPAIRED TO THE SATISFACTION OF THE OWNER AT THE CONTRACTOR'S EXPENSE.
- 12) GUARANTY AND REPLACEMENT: IF A SATISFACTORY STAND OF MAINTAINED TURF HAS BEEN PRODUCED AT THE TIME OF FINAL INSPECTION, IT SHALL BE GUARANTEED THROUGH ONE COMPLETE GROWING SEASON. IF RENOVATION AND/OR RESEEDING ARE REQUIRED AT THE END OF THE GUARANTEE PERIOD, THIS WORK SHALL BE DONE IN CONFORMANCE WITH THE REQUIREMENTS NOTED ABOVE. IF A SATISFACTORY STAND OF MAINTAINED TURF HAS NOT BEEN PRODUCED AT THE TIME OF FINAL INSPECTION, NECESSARY REPAIRS SHALL BE PERFORMED IN CONFORMANCE WITH THE REQUIREMENTS NOTED ABOVE. UPON COMPLETION OF THESE REPAIRS, THE TURF GRASS SHALL BE GUARANTEED AS NOTED ABOVE.


TECHNICAL NOTES FOR LOAM BORROW:

CLAY (LESS THAN 0.002 MM)

- 1) <u>SCOPE OF WORK:</u> FOR THIS PROJECT, THE WORK SHALL INCLUDE PLACING LOAM ON ALL AREAS TO RECEIVE PLANTS AND TURFGRASS SEEDING.
- 2) THE CONTRACTOR SHALL FURNISH A CERTIFIED LABORATORY REPORT SHOWING THE SOILS CLASSIFICATION AND NUTRIENT ANALYSIS OF REPRESENTATIVE SAMPLES OF THE LOAM THIS IS PROPOSED TO BE USED, INCLUDING THE EXTENT OF LIME AND FERTILIZER REQUIRED. ALL COSTS FOR SUCH WORK SHALL BE BORNE BY THE CONTRACTOR.
- 3) IN ACCORDANCE WITH THE SPECIFIC REQUIREMENTS OF THIS PROJECT, EXISTING ON—SITE SOIL MAY BE RE—USED AS LOAM BORROW ONLY IF IT MEETS THIS SPECIFICATION. EXISTING TOPSOIL THAT DOES NOT MEET THIS SPECIFICATION MAY BE RE—USED ONLY UP TO THE SUBGRADE ELEVATION WITHIN THE LIMITS OF AREAS TO RECEIVE NEW LOAM BORROW. THE CONTRACTOR SHALL FURNISH ALL REQUIRED LOAM BORROW, FROM OFF—SITE SOURCES, AS NECESSARY, TO COMPLETE THE PROJECT
- 4) SCREENED LOAM SHALL BE "FINE SANDY LOAM" OR "SANDY LOAM" DETERMINED BY MECHANICAL ANALYSIS (ASTM D-422) AND BASED ON THE "USDA CLASSIFICATION SYSTEM". SCREENED LOAM SHALL HAVE THE FOLLOWING

MECHANICAL ANALYSIS:		
TEXTURAL CLASS %	% OF TOTAL WEIGHT	AVERAGE 2
SAND (0.05 - 2.0 MM)	45 – 75	60
SILT $(0.002 - 0.05 \text{ MM})$	5 - 35	25

- 5) SCREENED LOAM SHALL BE A NATURAL PRODUCT CONSISTING PRIMARILY OF NATURAL TOPSOIL, FREE FROM SUBSOIL, AND OBTAINED FROM AN AREA THAT HAS NEVER BEEN STRIPPED BEFORE. SCREENED LOAM SHALL NOT CONTAIN LESS THAN FIVE PERCENT (5%) NOR MORE THAN TEN PERCENT (10%) ORGANIC MATTER. TO ADJUST ORGANIC MATTER CONTENT, THE SOIL MAY BE AMENDED, PRIOR TO SITE DELIVERY, BY THE ADDITION OF COMPOSTED LEAF MOLD OR PEAT MOSS. NO MIXING OR AMENDING OF LOAM IS PERMITTED ON SITE.
- 6) THE LOAM SHALL NOT BE DELIVERED IN A WET OR FROZEN CONDITION.
- 7) SCREENED LOAM SHALL CONSIST OF FERTILE, FRIABLE, LOAM CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH.
 LOAM SHALL BE WITHOUT ADMIXTURE OF SUBSOIL AND REFUSE. IT SHALL BE A HOMOGENEOUS MATERIAL FREE OF
 STONES GREATER THAN ONE—HALF (1/2) INCH IN THE LONGEST DIMENSION; FREE OF LUMPS, PLANTS, GRASS, ROOTS,
 STICKS, EXCESSIVE STONE CONTENT, DEBRIS, AND EXTRANEOUS MATTER AS DETERMINED BY THE OWNER.
- 8) SCREENED LOAM SHALL BE WITHIN THE PH RANGE OF 6.0 TO 6.5. IT SHALL BE UNCONTAMINATED BY SALT WATER, FOREIGN MATTER, AND SUBSTANCES HARMFUL TO PLANT GROWTH. THE MAXIMUM SOLUBLE SALT INDEX SHALL BE 100. SCREENED LOAM SHALL NOT HAVE LEVELS OF ALUMINUM GREATER THAN 200 PARTS PER MILLION.
- 9) SEE TURFGRASS NOTES FOR LIME AND FERTILIZER REQUIREMENTS FOR LAWN AREAS.
- 10) TOPSOIL STRUCTURE SHALL NOT BE DESTROYED THROUGH EXCESSIVE AND UNNECESSARY HANDLING OR COMPACTION. INAPPROPRIATE HANDLING LEADING TO THE COMPACTION OF DETERIORATION OF SOIL STRUCTURE WILL RESULT IN REJECTION OF TOPSOIL FOR USE.
- 11) AT NO TIME SHALL EQUIPMENT OR MATERIAL REST ON THE SOIL.
- 12) THE CONTRACTOR SHALL FURNISH AND SPREAD LOAM TO A MINIMUM 4—INCH DEPTH (AFTER SOIL SETTLEMENT) IN ALL LAWN AND PLANT BED AREAS. THE TOP OF THE SETTLED LOAM BORROW LAYER SHALL BE TO GRADES SPECIFIED ON THE DRAWINGS. NO COMPACTION SHALL BE REQUIRED BEYOND THAT EXTENT NECESSARY TO PLACE SOD OR TO PLANT TREES AND SHRUBS TO ENSURE AGAINST UNEVENNESS OR SETTLING BELOW ACCEPTED GROWTH LINES.




ISSUED
FOR
CONSTRUCTION

Andrews Survey & Engineering, Inc

Andrews Survey & Engineering, Inc.

and Surveying - Civil Engineering - Site Planning

P.O. Box 312, 104 Mendon Street
Uxbridge, Massachusetts 01569
P: 508-278-3897 F: 508-278-2289



J

LESON DE DE LES CONTRACTOR DE LA CONTRAC

PROJECT #: 19-793
ISSUE DATE: 02/03/2021
DRAWN BY: CHECKED BY: REVISIONS:

SHEET No.

C5.1

EROSION & SEDIMENT CONTROL PLAN

PART 1 - GENERAL 1.01 SUMMARY

A. FURNISH, INSTALL, AND MAINTAIN TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES, SUCH AS, BUT NOT NECESSARILY LIMITED TO, STRAW BALE AND SILT FENCE BARRIERS, RIPRAP, VEHICLE TRACKING PADS, DIVERSION CHANNELS AND BERMS, CHECK DAMS, STRATEGICALLY LOCATED STOCKPILES, SEDIMENT BASINS, MULCH, AND SEED MIX (HEREINAFTER "CONTROL MEASURES") ADEQUATE TO PREVENT THE CONVEYANCE OF EROSION PRODUCTS (E.G. SOIL, MULCH, SOD) OFF SITE, OR INTO ENVIRONMENTALLY SENSITIVE AREAS, OR INTO AREAS WHERE WORK WILL BE ADVERSELY IMPACTED. ENVIRONMENTALLY SENSITIVE AREAS INCLUDE, BUT ARE NOT NECESSARILY LIMITED TO, WETLANDS, TRIBUTARIES TO WETLANDS, WETLAND BUFFER ZONES, INTERMITTENT AND PERENNIAL STREAMS / RIVERS, AND THEIR ATTENDANT BUFFER ZONES.

ALL METHODS AND MATERIALS USED FOR EROSION CONTROL SHALL CONFORM TO THE REQUIREMENTS SET FORTH IN "EROSION AND SEDIMENT CONTROL GUIDELINES FOR URBAN AND SUBURBAN AREAS A GUIDE FOR PLANNERS, DESIGNERS, AND MUNICIPAL OFFICIALS" AS PUBLISHED BY THE MASSACHUSETTS DEPARTMENT OF ENVIRONMENTAL PROTECTION, BUREAU OF RESOURCE PROTECTION, UNLESS OTHERWISE APPROVED IN WRITING.

1. REFER TO DRAWINGS FOR LOCATION AND DETAILS OF LIMITS OF DISTURBANCE AND CONTROL MEASURES REQUIRED TO COMMENCE WORK. LIMITS OF DISTURBANCE SHALL BE MARKED WITH TAPE, SIGNS, OR ORANGE CONSTRUCTION FENCE PRIOR TO COMMENCING ANY LAND DISTURBANCE ACTIVITIES. CONTROL MEASURES WILL BE ADEQUATE ONLY FOR VEGETATION CLEARING. THE DRAWINGS ARE NOT INTENDED TO GRAPHICALLY DEPICT ALL CONTROL MEASURES THAT WILL BE REQUIRED TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A.

2. DEVISE AND EMPLOY CONTROL MEASURES THROUGHOUT THE DURATION OF PROJECT, OVER ALL AREAS DISTURBED OR UNDISTURBED BY CONSTRUCTION, AS NECESSARY TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A.

3. DEVISE AND EMPLOY TEMPORARY CONTROL MEASURES AS NECESSARY TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A, WHILE ALLOWING WORK TO PROCEED IN AN EFFICIENT, COST EFFECTIVE MANNER.

4. DEVISE, EMPLOY AND MAINTAIN CONTROL MEASURES UNTIL SUCH TIME AS THE ENTIRE SITE IS PERMANENTLY STABILIZED BY ESTABLISHED VEGETATION, FINISH LANDSCAPE MATERIALS, PAVED SURFACES, AND/OR ROOF AREA.

5. ONCE THE SITE IS PERMANENTLY STABILIZED AND CERTIFIED AS SUCH BY ENGINEER, REMOVE TEMPORARY CONTROL MEASURES WHILE PROTECTING STABILIZED SURFACES.

A. SUBMIT PRODUCT DATA, WARRANTY, AND TEST REPORTS AS INDICATED ON THE DRAWINGS.

B. SUBMIT SKETCH SHOWING LOCATIONS OF PROPOSED STOCKPILE AREAS, CONSTRUCTION ENTRANCES AND EROSION CONTROLS IF NOT SHOWN ON THE SITE PLAN OR DIFFERENT FROM THOSE LOCATIONS SHOWN ON THE SITE PLAN.

C. A SITE SPECIFIC SEQUENCE OF CONSTRUCTION FOR EACH PORTION OF THE SITE. NO PORTION OF THE SITE SHALL EXCEED FIVE (5) ACRES.

1.03 QUALITY ASSURANCE

A. COMPLY WITH GOVERNING CODES AND REGULATIONS. PROVIDE PRODUCTS FROM ACCEPTABLE MANUFACTURERS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

B. CONFORM TO CONDITIONS OF APPROVAL ISSUED BY REGULATORY AGENCIES INCLUDING, BUT NOT NECESSARILY LIMITED TO, LOCAL PLANNING BOARD, CONSERVATION COMMISSION, CITY COUNCIL, BOARD OF HEALTH, PUBLIC WORKS / HIGHWAY DEPARTMENT, STATE ENVIRONMENTAL PROTECTION DEPARTMENT, AND U.S. GOVERNMENT, ENVIRONMENTAL PROTECTION AGENCY. WHERE CONDITIONS OF REGULATORY APPROVAL DIFFER FROM REQUIREMENTS CONTAINED HEREIN OR ON THE DRAWINGS, COMPLY WITH THE MORE STRINGENT REQUIREMENT.

PART 2 - PRODUCTS

2.01 MATERIALS

A. STRAW BALES: WEED FREE DRY GRASS OR STRAW, MACHINE BOUND WITH JUTE OR WIRE, APPROXIMATE SIZE EACH BALE 42" X 16" X 16". EACH BALE SHALL BE STAKED WITH A MINIMUM OF TWO 24" LONG HARDWOOD STAKES. NOTE: HAY SHALL NOT BE USED.

B. SILTSOXX: FILTREXX NORTHEAST SYSTEMS OR APPROVED EQUAL.

SILT FENCE: NON-WOVEN, UV-RESISTANT, POLYPROPYLENE FABRIC, FLOW RATED AT 10 GPM/SF MINIMUM, GRAB TENSILE RATED AT 124 POUNDS MINIMUM, WITH INTEGRAL STAKE LOOPS, AND HARDWOOD STAKES. USE NO. 2130 BY AMOCO FABRICS & FIBERS, OR APPROVED EQUAL.

D. MULCH: ORGANICS INCLUDING STRAW, PROCESSED PINE / HEMLOCK TWIGS AND NEEDLES.

E. SEED MIXES: SHALL MEET THE REQUIREMENTS OF MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES, LATEST EDITION SECTION 6.03.0 OR 6.03.1 AS APPROPRIATE.

F. EXCELSIOR BLANKET: CURLED WOOD FIBER ON PHOTODEGRADABLE EXTRUDED PLASTIC MATRIX, 80% OF FIBERS 6-INCHES LONG OR LONGER, WEIGHT 0.975 POUNDS / SY, CONTAINING NO CHEMICAL ADDITIVES. USE CURLEX I BLANKET BY AMERICAN EXCELSIOR COMPANY, OR APPROVED

G. ROCK RIPRAP: SOUND, ANGULAR, 6-INCH MINUS PROCESSED ROCK, BLAST ROCK, OR

H. CRUSHED STONE: SOUND, ANGULAR, 2-INCH MINUS PROCESSED CRUSHED STONE.

PART 3 - EXECUTION

3.01 THROUGHOUT CONSTRUCTION

A. DEVISE WORK SEQUENCE SO AS TO LIMIT DRAINAGE AREA THAT IS TRIBUTARY TO DISTURBED AREAS. DEVISE, EMPLOY, AND MAINTAIN CONTROL MEASURES SUCH AS DIVERSION CHANNELS AND BERMS, STRATEGICALLY LOCATED STOCKPILES, AND SEDIMENT BASINS TO SUBDIVIDE DRAINAGE AREAS INTO SMALL, MANAGEABLE SUBAREAS, THEREBY MINIMIZING RUNOFF AND THE POTENTIAL FOR EROSION.

B. MAINTAIN BARRIER AT LIMIT OF WORK AND PROTECT EXISTING VEGETATION / FACILITIES OUTSIDE OF LIMIT OF WORK.

C. MAINTAIN SPARE MATERIAL STOCKPILES FOR IMMEDIATE EMPLOYMENT / REPAIR / EXPANSION OF CONTROL MEASURES. AT A MINIMUM, SUCH MATERIALS SHALL INCLUDE HAY BALES, SILT FENCE AND STAKES, AND CRUSHED STONE.

D. INSPECT AND MAINTAIN EFFECTIVENESS OF CONTROL MEASURES BY REPAIRING AS NECESSARY TO ENSURE INTENDED FUNCTION; BY SUPPLEMENTING AS NECESSARY FOR ADEQUATE EXTENT; BY REMOVING TRAPPED PRODUCTS OF EROSION AS NECESSARY TO MAINTAIN EFFECTIVE TRAP VOLUME.

E. LIMIT EXTENT OF WORK AREA SO THAT ALL DISTURBED AREAS CAN BE STABILIZED WITH CONTROL MEASURES WITHIN A 24-HOUR PERIOD.

F. INSTALL CONTROL MEASURES AS SOON AS PRACTICABLE AFTER EACH MANAGEABLE PORTION OF EARTHWORK IS COMPLETE. EMPLOY TEMPORARY MEASURES AS NECESSARY TO STABILIZE DISTURBED AREAS, EVEN WHERE SUBSEQUENT CONSTRUCTION OPERATIONS MAY REQUIRE RE-DISTURBANCE.

PART 3 - CONTINUED

G. WHEN INTENSE RAINFALL IS EXPECTED, CONSIDER, DEVISE, AND EMPLOY REINFORCING CONTROL MEASURES PRIOR TO THE RAINFALL EVENT TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A. IF NECESSARY, EMPLOY TEMPORARY CONTROL MEASURES ON MATERIAL STOCKPILES TO COUNTERACT POTENTIAL SEDIMENT TRANSPORT DURING INTENSE RAINFALL.

H. WHEN VEHICLE REFUELING IS REQUIRED ON SITE, CONDUCT REFUELING OPERATIONS OUTSIDE OF ENVIRONMENTALLY SENSITIVE AREAS.

I. PROPERLY DISPOSE OF DEBRIS, SOLID WASTE, TRASH, AND CONSTRUCTION WASTE / BYPRODUCTS OFF SITE.

J. SWEEP ON-SITE PAVED AREAS AND OFF-SITE STREETS AS NECESSARY TO PREVENT SILT AND DEBRIS ORIGINATING ON SITE FROM ENTERING CLOSED DRAINAGE SYSTEMS AND / OR ENVIRONMENTALLY SENSITIVE AREAS. WHEN NECESSARY UTILIZE WATER SPRAYING, SURFACE ROUGHENING AND/OR APPLY POLYMERS, SPRAY-ON TACKIFIERS, CHLORIDES AND BARRIERS FOR

K. INSPECT EROSION CONTROLS DAILY THROUGHOUT CONSTRUCTION REPAIR DAMAGED CONTROLS

3.02 SITE PREPARATION AND ACCESS

A. WALK SITE AND IDENTIFY LOCATIONS OF LIMIT OF WORK AND ENVIRONMENTALLY SENSITIVE AREAS. ESTABLISH CONSTRUCTION STAGING AREA, LOCATED BEYOND ENVIRONMENTALLY SENSITIVE

B. INSTALL CONTROL MEASURES AS SHOWN ON THE DRAWINGS, INCLUDING THOSE DEFINING THE

C. LIMIT VEHICULAR TRAFFIC TO AND FROM SITE TO MINIMIZE TRANSPORT OF SEDIMENT.

3.03 CLEARING, GRUBBING, AND STRIPPING A. SCHEDULE GRUBBING AND STRIPPING TO OCCUR IMMEDIATELY PRIOR TO EARTH DISTURBANCE. DEPENDING ON SITE AREA, CONSIDER MULTIPLE GRUBBING PHASES, SEQUENCED TO TAKE

ADVANTAGE OF THE EROSION PREVENTION POTENTIAL OF EXISTING VEGETATIVE COVER. B. MINIMIZE THE AREA OF EXISTING VEGETATION REMOVED WHEREVER POSSIBLE. NO GREATER

THAN FIVE (5) ACRES SHALL BE UNSTABLE AT ANY TIME. C. LOCATE AND SIZE STOCKPILES TO MINIMIZE EROSION POTENTIAL, TAKING ADVANTAGE OF

TERRAIN SLOPE AND ASPECT, WHERE APPROPRIATE.

D. PROTECT VEGETATION, INCLUDING ROOT SYSTEMS, BEYOND LIMIT OF CLEARING.

E. PROCESS TIMBER, STUMPS, SLASH, AND BRUSH SO AS TO PROTECT ENVIRONMENTALLY SENSITIVE AREAS AND INSTALLED CONTROL MEASURES. PROPERLY DISPOSE OF EXCESS OFF SITE. BURIAL OF STUMPS ON SITE IS PROHIBITED.

3.04 EXCAVATION FOR BUILDING FOUNDATIONS AND UTILITIES

A. DEVISE AND INSTALL CONTROL MEASURES ADEQUATE TO HANDLE DISCHARGES AND TRAP SEDIMENT FROM FOOTING SUMP AND WELL POINT PUMPS PRIOR TO EXCAVATION.

B. ARMOR SUMP PUMP DISCHARGE LOCATIONS TO PREVENT EROSION AT POINT OF DISCHARGE AND AREAS DOWNSTREAM.

C. IF FOUNDATION EXCAVATIONS GRADE TO DAYLIGHT ON THE LOW SIDE, DEVISE AND INSTALL CONTROL MEASURES TO HANDLE SURFACE AND GROUNDWATER FLOW FROM EXCAVATION LOW

D. STOCKPILE EXCAVATED MATERIALS TO BAFFLE OVERLAND RUNOFF, AVOIDING THE CREATION OF LENGTHY PATHS OF CONCENTRATED RUNOFF. STOCKPILE SLOPES SHALL NOT EXCEED 2:1.

E. BACKFILL UTILITY TRENCHES AS SOON AS PRACTICABLE TO PREVENT FLOODING, SLOUGHING, POTENTIAL OVERFLOW, AND REPETITIVE EARTH DISTURBANCE.

3.05 SITE GRADING

A. WHERE APPLICABLE, FOLLOW EXCAVATION AND FILL PRACTICES SHOWN ON DRAWINGS TO LOCALIZE AND MINIMIZE EROSION.

B. MONITOR SEDIMENT VOLUME IN TEMPORARY SEDIMENT BASINS AND AT DIVERSION BERMS AND CHECK DAMS. IN ALL AREAS EXCEPT THOSE THAT DO NOT PRESENT POTENTIAL PROBLEMS WITH REGARD TO FUTURE SOIL STABILITY, DRAINAGE, OR BEARING CAPACITY, REMOVE AND PROPERLY DISPOSE OF TRAPPED SEDIMENT BEFORE BRINGING SITE TO FINAL SUBGRADE.

C. EXPOSED SOILS SHALL BE PERMANENTLY STABILIZED WITHIN FIVE (5) BUSINESS DAYS OF COMPLETION OF CONSTRUCTION OF A GIVEN AREA. EXPOSED AREAS WHERE NO WORK HAS OCCURRED FOR FOURTEEN (14) DAYS SHALL BE TEMPORARILY STABILIZED WITH HYDROSEED OR OTHER APPROVED METHOD.

D. SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED IMMEDIATELY AFTER COMPLETION. 3.06 LANDSCAPING

A. COMPLETE LANDSCAPING AS SOON AS POSSIBLE AFTER COMPLETION OF FINAL SUBGRADE.


B. IMMEDIATELY AFTER PLACEMENT OF TOPSOIL, STABILIZE WITH CONTROL MEASURES INCLUDING, BUT NOT NECESSARILY LIMITED TO, SEED MIX, MULCH, AND / OR BLANKET.


C. PERMANENT SEEDING MAY BE PERFORMED IN THE SPRING PRIOR TO JULY 1 AND IN BETWEEN AUGUST 1 AND OCTOBER 15. PERMANENT SEEDING AT OTHER TIMES SHALL BE APPROVED AND SHALL ONLY BE ALLOWED WITH AN APPROVED MULCHING AND IRRIGATION PROGRAM.

GENERAL SEQUENCE OF CONSTRUCTION PLACE LIMIT OF WORK BARRIERS, FENCES, CONSTRUCTION ENTRANCES AND REQUIRED


- FENCING & SIGNS. CONSTRUCT SEDIMENT TRAPS & BARRIERS AND PLACE OTHER CONTROLS, DIVERSION
- TRENCHES, PERIMETER DIKES, WATER BARS & OUTLET PROTECTION.
- ESTABLISH STOCKPILE AND STAGING AREAS. CUT TREES AND SHRUBS AND REMOVE FROM SITE OR STOCKPILE AND PROTECT STOCKPILE(S) BY APPROVED METHODS.
- 5. EXCAVATE STUMPS AND REMOVE FROM SITE OR STOCKPILE AND PROTECT STOCKPILE(S) BY APPROVED METHODS.
- BEGIN EARTHWORKS, ESTABLISH, STABILIZE AND PROTECT CUT AND FILL SLOPES.
- BEGIN INSTALLATION OF OTHER UTILITIES. ESTABLISH COVER, STABILIZE AND PROTECT AREAS DISTURBED FOR UTILITY INSTALLATION.
- BEGIN EXCAVATION FOR STRUCTURES. STOCKPILE AND PROTECT EXCAVATED MATERIALS. BACKFILL FOUNDATIONS STABILIZE ALL DISTURBED AREAS AND REMOVE EXCESS SOIL FROM
- 10. PERFORM SITE WORK IN ACCORDANCE WITH "EROSION AND SEDIMENT CONTROL
- <u>REQUIREMENTS.</u> PART 3 EXECUTION". 11. VERIFY ALL AREAS HAVE BEEN STABILIZED, RE-SEED EXPOSED SOILS.
- 12. CLEAN CATCH BASINS AND STORM DRAINS. REMOVE SOILS FROM SITE. 13. REMOVE ALL EROSION CONTROLS, LIMIT OF WORK BARRIERS, FENCES, CONSTRUCTION


ENTRANCES, SIGNS AND SWEEP PAVED AREAS.





EXCAVATION PROCEDURE SCALE: N.T.S.





STOCKPILE TO BE LOCATED IN AN AREA


AGAINST EROSION TOWARDS SENSITIVE AREAS


WHICH PROVIDES MAXIMUM PROTECTION


TEMPORARY STOCKPILE

CONTINUOUS STAKED STRAW BALE DIKE

PLACED DOWNGRADIENT OF STOCKPILE











Andrews Survey & Engineering, Inc. Land Surveying - Civil Engineering - Site Planning P.O. Box 312, 104 Mendon Street Uxbridge, Massachusetts 01569 P: 508-278-3897 F: 508-278-2289




PROJECT #:. <u> 19-793</u> 02/03/2021 ISSUE DATE: DRAWN BY: CHECKED BY: **REVISIONS:**

SHEET No.

EROSION & SEDIMENT CONTROL NOTES & DETAILS





THE APPLICABLE REGULATIONS OF THE AMERICANS WITH DISABILITIES ACT

3. THE MAXIMUM ALLOWABLE SIDEWALK AND CURB RAMP CROSS SLOPES

4. THE MAXIMUM ALLOWABLE SLOPE OF ACCESSIBLE ROUTES, EXCLUDING

THE MAXIMUM ALLOWABLE SLOPE OF ACCESSIBLE ROUTE CURB RAMPS

6. MAINTAIN A MINIMUM OF 3 FEET CLEAR AT ANY PERMANENT OBSTACLE IN ACCESSIBLE ROUTES (I.E., TREE WELLS, HYDRANTS, UTILITY POLES, SIGNS,

RAMP CONSTRUCTION SHALL CONFORM TO TYPICAL SIDEWALK SECTION.

10. ALL CURBING AT RAMPS SHALL BE VERTICAL CURBING SET FLUSH WHERE

1. ALL RAMPS SHALL BE CEMENT CONCRETE WITH ROUGHENED NON-SLIP

7.5% [1]

BUILDING OR OTHER

8 SLOPED GRANITE CURB (SGC)
SCALE: N.T.S.

INALTERABLE CONDITION

9. WHERE ACCESSIBLE ROUTES ARE LESS THAN 5' IN WIDTH (EXCLUDING CURBING) A 5'X5' PASSING AREA SHALL BE PROVIDED AT INTERVALS NOT

(ADA) OF JANUARY 1992.

CURB RAMPS SHALL BE 5%.

. GRADE BASE OF RAMP TO PREVENT PONDING.

SHALL BE 2% (1% MIN.)

TO EXCEED 200 FEET.

SIDEWALK

IT ABUTS ROADWAY.

SHALL BE 7.5%.

* = TOLERANCE FOR CONSTRUCTION $\pm 0.5\%$

** = TRANSITION LENGTH BASED ON DESIGN

*** = DETECTABLE WARNING PANEL LOCATED

ROADWAY EDGE (GUTTER LINE). TRUNCATED

DOMES TO BE ALIGNED WITH DIRECTION OF

NOT LESS THAN 6" OR MORE THAN 24" FROM


6'-6"
LOW SIDE TRANSITION


BUILDING OR OTHER


INALTERABLE CONDITION


SIDEWALK

SLOPE OR ROADWAY SEE M/E 107.9.0












ROADWAY DOWNGRADE

,LANDING/TURNING AREA, LEVEL WITH STREET &

DETECABLE WARNING








ISSUED


FOR

CONSTRUCTION

PROJECT #: ISSUE DATE: DRAWN BY: CHECKED BY:_	02/03/2021
REVISIONS:	


SHEET No. CONSTRUCTION DETAILS





ISSUED FOR CONSTRUCTION

Andrews Survey & Engineering, Inc. Land Surveying - Civil Engineering - Site Planning P.O. Box 312, 104 Mendon Street Uxbridge, Massachusetts 01569 P: 508-278-3897 F: 508-278-2289



PROJECT #:_ ISSUE DATE:_ DRAWN BY: CHECKED BY:_ **REVISIONS:**

SHEET No.

CONSTRUCTION DETAILS